RESIDENTIAL ZONE

Single houses with some infill housing will occupy a large portion of this precinct, in line with the R-Codes R30 standards. The retention of original housing and the promotion of selective sensitive redevelopment consistent with existing style, scale and character will consolidate the area as to a low to medium density neighbourhood.

In selected areas (indicated on the Precinct Map) redevelopment will be permitted in accordance with the R60 and R80 standards; permitting single houses as well as grouped and multiple dwellings at a higher density.

The application of the R-Codes and design and development guidelines shall ensure new buildings in the lower density areas reflect the existing traditional characteristics of the precinct. Buildings are to be set back from all boundaries and surrounded by landscaped spaces. While the effect of traffic on dwellings fronting roads should be minimised through appropriate design measures, all development shall face the street in the traditional manner.

Priority will be given to ensuring that new development, particularly infill and development at higher densities, does not result in undue loss of privacy or amenity for existing residents.

New development fronting main roads must take vehicular access from a laneway or other street where possible and where residential amenity will not be diminished.

RESERVES

by local residents.

RAPHAEL PARK and HAWTHORNE PARK

These areas shall continue in their role

as recreational parkland for use primarily

The land will be used, maintained and

development of any new buildings within

enhanced as parklands. The

these areas will generally not be permitted unless they are small in bulk and scale, unobtrusive in their setting,

and only if necessary to meet local

all existing landscape elements, particularly the large Morton Bay Fig

Trees in Raphael Park.

recreational needs. No activity or action will be permitted which may destroy the integrity of the recreation areas, including

USE OF LAND

As indicated in the Zoning Table in the Scheme Text and outlined below for a Residential Zone:

	_
Replaced by AMDT 80 GG 18/04/19	
Zon	
Use Class	
Consulting Rooms, Day Care Centre	
Convenience Store, Service Station	
Educational Establishment, Place of Worship	,
Fast Food Outlet, Restaurant	
General Industry, Transport Depot	
Hazardous Industry, Noxious Industry	
Home Occupation	7
Home Office	
Hospital, Nursing Home, Residential Building	,
Hotel, Motel, Tavern	
Light Industry	
Liquor Store - Small	
Liquor Store - Large	
Lodging House, Serviced Apartment	
Massage Rooms	T
Motor vehicles and Marine Sales Premises Open Air Sales and Display	
Nightclub Nightclub	H
Office	t
Restricted Premises	t
	+

Footnote:

Service Industry

Shop

Showroom

Multiple Dwelling

Warehouse

1. Multiple Dwellings are only permitted in areas coded R40 and above, and in addition are subject to clause 22 of the Scheme Text - Special Application of the R-Codes.

Single House, Group Dwelling, Aged or

Dependent Persons' Dwelling,

The symbols used in the cross reference in the Zoning Table have the following meanings:

"P" (Permitted Use): means that the use is permitted by the Scheme.

"AA" (Discretionary Use): means that the use is not permitted unless the Council has granted planning approval.

"X" (Prohibited Use): means a use that is not permitted by the Scheme.

Note: If the use of the land for a particular purpose is not specifically mentioned in the Zoning Table and cannot be determined as falling within the interpretation of one of the Use Class categories Council may consider it an unlisted (ie

discretionary) use requiring that the

advertising procedures referred to in

clause 28 of the Scheme Text be

DEVELOPMENT STANDARDS

Development shall generally be in accordance with the R-Codes (where applicable) and any relevant planning

Building Height -

The building height on land bounded by Canning Highway, Gloucester Street, Washington Street and the right-of-way located between Canning Highway and Armagh Street, coded Residential R60, shall not exceed 3 storeys (11.25m).

The building height on land bounded by Canning Highway, Washington Street and Heirisson Way, coded Residential R80, shall not exceed 5 storeys (18.75m).

The building height on land bounded by McMaster Street, Berwick Street and Leonard Street shall be as follows:

For lot frontages to Leonard Street:

A significant portion of building, to a maximum height of 3 storeys (11.25m), is to be located between a 4.0m minimum front setback and a maximum 6.0m front setback. Any portion of building above 3 storeys (11.25m) is to be setback a minimum of 12.0m from the front boundary, and shall be a maximum height of 6 storeys (22.5m).

For lot frontages to all streets other than Leonard Street:

A maximum building height of 6 storeys (22.5m) with a minimum front setback of

Where the lot has a boundary to a secondary street the secondary street elevation is to be appropriately articulated.

Development on Lots 14, 15 and 41 Armagh Street to be generally in accordance with the R-Codes and the relevant

planning policies contained in the Town Planning Scheme. Development to be in accordance with the development standards for R30, or in the case of where the subject lots are amalgamated into one lot, development to be in accordance with R60 with the following specific standards applying:

 Building Height Building height shall be limited to 3 storeys (11.25m), other than any portion of building within 8.0m of the boundary with Lot 42 Armagh Street, for which a maximum building height of 2 storeys (7.5m) applies.


Setback

Setback to Berwick Street may be reduced to less than 3.0m where the proposed development is considered to result in a good urban design

POLICY NOTE: Design and development guidelines for residential development in the Raphael Precinct have been adopted by the Council and are included in a planning policy.

Access and Parking

SCALE 1:5,000





Precinct Boundary

TOWN OF VICTORIA PARK SCHEME RESERVES

Parks and Recreation

Public Purposes

Primary School

TOWN OF VICTORIA PARK **SCHEME ZONES**

Residential



R-Code

TOWN OF VICTORIA PARK **TOWN PLANNING SCHEME No.1** RAPHAEL PRECINCT

PRECINCT PLAN P5

Updated on 14 April 2019

AMENDMENT N º.	GAZETTAL DATE	AMENDMENT N.º.	GAZETTAL DATE
3.	2 February 2001	75.	23 June 2017
6.	8 October 2002	77.	19 June 2018
50.	13 July 2012	80.	14 April 2019
59.	21 June 2013		
61.	14 November 2014		

This Precinct Plan describes the Council's town planning intentions for this precinct. It contains a Statement of

The Raphael Precinct shall remain as a residential precinct containing many fine examples of houses from past eras.

STATEMENT OF INTENT

The precinct is and should remain a low to medium density housing area for the larger part. Infill development and the redevelopment of corner lots may be appropriate, although not to the detriment of the existing character of the area and of the existing quality

Higher densities, allowing multiple units and grouped housing are permitted in selected areas of the precinct.

Further non-residential uses will only be permitted where they are small in scale, maintain the residential character and provide for day to day local needs.

The precinct should remain a visually attractive area and have a pleasant atmosphere characterised by low to medium scale architecture, buildings facing the street in the traditional manner and set in landscaped surrounds. The retention of structurally sound original houses and healthy mature trees will be a priority in order to maintain the existing residential character and streetscapes.

Streets within the precinct will be enhanced and maintained so that they contribute to its pleasant environment. In particular, Council will endeavour to discourage the movement of commercial traffic into residential streets from main roads adjacent to the precinct. Safe,

accessible movement for pedestrians, cyclists, public

precinct.

transport and private vehicles is an important aim for the

1. Planning polices which contain guidelines for the

for the development of land and buildings.

This Precinct Plan should be read together with: -

HOW IT WORKS

development and use of land which apply to more than one precinct. References are given in this Precinct Plan to those policies.

Intent which applies to the whole Precinct and several

that is seen to be appropriate for the precinct.

other statements which apply to specific areas within the

In this Precinct Plan you will also find information about

the purposes for which land may be used and guidelines

Precinct. These statements summarise the kind of future

2. The Scheme Text which contains legal and administrative provisions regarding the use and development of land.

In order to determine how a particular lot is affected by the above, you will need to refer to that lot on the map and the related text in this Precinct Plan. Where a property is located on or near the Precinct boundary it may also be necessary to consult the neighbouring Precinct/s. It should also be noted that from time to time, the Town Planning Scheme may be subject to amendments.

You are reminded that before land and buildings can be developed or used for another purpose it will probably be necessary to make a planning application and receive approval from the Council.

Enquiries concerning this Precinct Plan or general planning matters should be directed to the Council's Planning Department.

ADOPTION

Adopted by resolution of the Council of the Town of Victoria Park at the Ordinary Meeting of the Council held on the 9th day of August 1994.

J A E LEE MAYOR

J M BONKER CHIEF EXECUTIVE OFFICER

FINAL ADOPTION

Adopted for final approval by resolution of the Council of the Town of Victoria Park at the Ordinary Meeting of the Council held on the 11th day of August 1998 and the seal of the Municipality was pursuant to that resolution, hereunto affixed in the presence of :

J A E LEE MAYOR

J M BONKER CHIEF EXECUTIVE OFFICER

RECOMMENDED FOR FINAL APPROVAL

CHAIRMAN OF THE WESTERN AUSTRALIAN PLANNING COMMISSION

FINAL APPROVAL GRANTED

MINISTER FOR PLANNING